





#### NTA Role for Active Travel Projects



- Since 2021, the NTA's Approving Authority role in urban centres
  was extended to the financing and construction of active travel
  projects developed by Local Authorities throughout the country,
  other then Greenway projects.
- The NTA is responsible for funding and securing the delivery of Urban Greenways. Urban Greenways are identifiable as having a <u>high commuting function</u> in addition to recreational and amenity use.
- The NTA works in partnership with TII, and the Local Authorities, on coordinating and delivering major rural Active Travel and Greenway projects, in a manner that is coherent with those in urban areas.








# € million

#### **Active Travel Investment 2022**




Region	Number of Active Travel Projects		
Greater Dublin Area	348		
Regional Cities	218		
Rural Local Authorities	442		
Campuses, Hospitals, Education Insts.	18		
Total	1026		





#### Outcomes for 2021







#### Outcomes for 2021





>7,000 Cycle Parking Stands



>150km Pedestrian Facilities



Safe Routes to School Programme
Started



>€10m on Outdoor Infrastructure



>90km Cycle Facilities





















#### Project Approval Guidelines




#### Phase 2 Concept and Development

• For NTA funded Active Travel Projects on National Roads, TII shall be consulted from an early stage in regard to the scheme development. A dedicated email address has been set up to initiate consultation: activetravel@tii.ie

#### Phase 3 Preliminary Design

- A submission to the TII Departures Portal will be required for all schemes on National Roads (DN-GEO-03030)
- Queries: infodeps:@tii.ie







#### Project Approval Guidelines



#### Phase 4 Statutory Process

- Section 38 (5) of the Roads Act states that 'Traffic calming measures shall not be provided or removed in respect of a national road without the prior consent of the National Roads Authority
- In accordance with the provisions of the Planning and Development Act 2000 (as amended) TII is a Statutory Consultee for development impacting National Roads








# Quality Audits & Road Safety Audits





#### Design Manual for Urban Roads and Streets Street Design Audit

Prepared in respect of (insert project description)

Prepared try: (insert company/organization names)

Date: (insert date)



Table A - Road Safety (RS) and Quality Audit (QA) Stages

Type and Complexity of Scheme	Stage F	Stage 1	Stage 2	Stage 3	Stage 4
Schemes/Works with estimated Construction Cost greater than €0.5m incl. VAT	RS and QA*	RS and QA	RS and QA	RS	RS
Schemes/Works with estimated Construction Cost less than €0.5m incl. VAT		RS and QA		RS	

<sup>\*</sup> To be carried out at the discretion of the Local Authority depending on the complexity and specific situation in each case.






# **Zebra Crossing Pilot**




- Current Zebra Crossing standard requires electricity connections. This restricts possible locations and has programme implications.
- Ongoing power requirements and maintenance have environmental and financial costs.
- Need for more 'controlled' crossing locations to supplement existing signalised crossings at junctions.
- NTA Cycling Design Office (CDO) tasked with carrying out review of international experience and recommending potential alternative layout for Zebra Crossings.



#### **Zebra Crossing Elements**



Flashing (Belisha)
Beacons + Stripes
Used mainly in
Ireland, UK and
New Zealand





Pedestrian Crossing Information Sign + Stripes

Used in most of Continental Europe (e.g. Netherlands, France, Germany, Austria, Italy)





Pedestrian
Crossing Warning
Sign + Stripes

Used in USA and Australia







### Potential New Zebra Crossing Layout



- Mandatory zebra road markings as existing.
- Optional Belisha Beacons or Zebra Crossing Traffic Sign similar to European examples.
- Fluorescent border on sign to increase visibility.





# Zebra Crossing Pilot - Trial Sites



• 4 sites in Dun Laoghaire-Rathdown County Council Area.

• 4 sites in Limerick City and County Council.



# Zebra Crossing Pilot - Indicative Programme



- Agree trial sites and monitoring methodology Complete
- Pre-pilot surveys –Complete
- Detailed Design and Construction Tender Complete
- Legislation Amendments September 2022
- Construction works October 2022
- 9-month Pilot –November to July 2023
- Post-pilot surveys April/May 2023
- Assessment and reporting Summer 2023











- The NTA has a number of contractors trialling colour asphalt mixes.
- Trial shown in photo includes:
  - Two different colouring approaches one with 3% iron oxide powder (purple) and one with 3% iron oxide (pellets).
  - Both SMA/10 also contain 15% RAP (recycled asphalt pavement) and 5% waste plastic (finely shredded).
     Polymer modified bitumen, no cellulose fibres.
- PMS providing technical support.



### **Precast Kerbing**



- The NTA is in discussions with a number of suppliers on providing various types of precast kerbing, either importing, or manufacturing locally.
  - Dutch entrance kerb;
  - Concrete dividing kerbs; and
  - Forgiving kerbs.








## Completed






- Requirement of National Sustainable Mobility Policy, Core Action
   No. 28
- County Cycle Network (CCN) Plans are intended to form a comprehensive cycle network for all cycle user types across each county in Ireland and to develop on from the cycle network proposed for the counties in the Greater Dublin Area (GDA).
- Includes county wide plans that link urban areas, and also urban plans for all towns above a population of 5,000.
- Draft Plans to be published for public consultation in October
   2022.


# Completed
















- Draft content currently being reviewed by international expert group (Dutch, Danish, UK input);
- Submission of draft version to Department of Transport (and Transport Infrastructure Ireland) shortly;
- Stakeholder consultation on draft final version Q4 2022;
- Legislative Changes will be required; and
- Training Programme by NTA for LA teams, agencies and consultancies to be developed fro H1 2023.



# Progress Uprate

National Cycle Manual





#### Key features:

- Cycle track 60mm below footpath level
- Cyclists yield to pedestrians here
- Raised pedestrian zebra crossing
- 4. Cyclists ramping down here
- Protected waiting and passing cyclists area 60mm below footpath level here Protected kerb island / build-out with potential SUDS feature
- 7. Gentle ramp from road level to protected waiting and passing cyclists area
- 8. Ramp down to road level and cyclist stop line
- Dedicated cyclist crossing with elephants footprints
   Pedestrian refuge area
- 11. Overrun area with roughened surface and 50mm kerbface

- Waiting turning vehicle area (5m)
   SUDS / public realm greening opportunities
   Ramp down to cycle track level from raised zebra crossing

