ADVICE NOTE 4 - Quality Audits

What is it?

Overarching audit which integrates existing audits

Key Features

- Transparent process to ensure needs of all users are addressed
- Check re delivery of Project Objectives
- Balanced resolution of design issues

Intention not to create another layer of documentation

ADVICE NOTE 4 - Quality Audits

Content of a Quality Audit

Individual Design Audits

- DMURS Street Design Audit
- Road Safety Audit
- Other Audits

Quality Audit Report

ADVICE NOTE 4 - Quality Audits

Quality Audit Report or DMURS Street Design Audit?

- DMURS Street Design Audit is always required
- Quality Audit required for larger, more complex projects
- Choose audits to suit project
- Identify issues which need to be resolved at planning stage

Quality Audit – Example






Cork Co Co CPIU - Multi disciplinary team

Issues to be addressed

- Town has lost sense of place
- Unattractive car dominated public space
- Public realm cluttered with signage, etc
- Very poor accommodation of pedestrians
- Poor permeability
- Heritage lost rather than celebrated
- Lack of interaction with surrounding context
- No space for community events







Holistic Design Approach


Mobility Plan

Lighting supports urban design principles


- **Permeability**
- **Integration**
- **Social interaction**








Zones 3 & 6 Existing plan



Project Objectives

- Regeneration Project
- Placemaking and heritage led
- Encourage socio economic redevelopment
- Pedestrian priority
- Inclusive design for all users
- Address well being / Covid issues
- Climate mitigation



Design Audits

- DMURS Street Design Audit
 - Connectivity
 - Self regulating streets
 - Pedestrian and cycling environment
 - Visual quality

a mechanism to check against the DMURS guidance

template at <u>www.dmurs.ie</u>

Road Safety Audit

Cycling audit?

Conservation Impact Audit

Pedestrian audit (PERS or DCC space calculator)?


Accessibility Audit





Issue: Loading bay on pedestrian desire line
Resolution: Relocate MID spaces, move loading bay
QA Recommendation: Bollard (hazard to MI users) removal
and replacement with trees










Resolution: Change to level raingardens with intermittent bridge access







Conservation Report: Design Guidance


- Historic Economy of Design
- Materials & Finishes
 - Gravel & Hoggin
 - Cobbles, setts, kerbs
 - Flagstones, banding, fans
- Street Furniture











With thanks to
Giula Vallone, Cork Capital Projects Implementation Unit;
John Hegarty, Conservation Architect;
Fiona Bohane, Cork National Road Design Office;
National Library of Ireland

Conclusion

- Clearly identify project objectives
- Audits appropriate to project
- DMURS is people centred design
- Stakeholder consultation is important
- Multi-disciplinary approach essential
- There are many ways to solve issues
- Use a two stage process
- Aim is to solve problems, while preserving project intent